

FORM PTO-1390
(REV. 9-2001)

U.S. DEPARTMENT OF COMMERCE PATENT AND TRADEMARK OFFICE

ATTORNEY'S DOCKET NUMBER

**TRANSMITTAL LETTER TO THE UNITED STATES
DESIGNATED/ELECTED OFFICE (DO/EO/US)
CONCERNING A FILING UNDER 35 U.S.C. 371**

077306.0101

U.S. APPLICATION NO. (If known, see 37 CFR 1.5)

10/030020

INTERNATIONAL APPLICATION NO.

PCT/EP00/05703

INTERNATIONAL FILING DATE

June 21, 2000

PRIORITY DATE CLAIMED

June 24, 1999

TITLE OF INVENTION

Method and Device for the Production of an Essentially Continuous Fine Thread

APPLICANT(S) FOR DO/EO/US

Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:

1. ☒ This is a **FIRST** submission of items concerning a filing under 35 U.S.C. 371.
2. ☐ This is a **SECOND** or **SUBSEQUENT** submission of items concerning a filing under 35 U.S.C. 371.
3. ☒ This is an express request to begin national examination procedures (35 U.S.C. 371(f)). The submission must include items (5), (6), (9) and (21) indicated below.
4. ☐ The US has been elected by the expiration of 19 months from the priority date (Article 31).
5. ☒ A copy of the International Application as filed (35 U.S.C. 371(c)(2))
 - a. ☒ is attached hereto (required only if not communicated by the International Bureau).
 - b. ☐ has been communicated by the International Bureau.
 - c. ☐ is not required, as the application was filed in the United States Receiving Office (RO/US).
6. ☒ An English language translation of the International Application as filed (35 U.S.C. 371(c)(2)).
 - a. ☒ is attached hereto.
 - b. ☐ has been previously submitted under 35 U.S.C. 154(d)(4).
7. ☒ Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371(c)(3))
 - a. ☒ are attached hereto (required only if not communicated by the International Bureau).
 - b. ☐ have been communicated by the International Bureau.
 - c. ☐ have not been made; however, the time limit for making such amendments has NOT expired.
 - d. ☐ have not been made and will not be made.
8. ☒ An English language translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371 (c)(3)).
9. ☒ An oath or declaration of the inventor(s) (35 U.S.C. 371(c)(4)).
10. ☐ An English language translation of the annexes of the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371(c)(5)).

Items 11 to 20 below concern document(s) or information included:

11. ☐ An Information Disclosure Statement under 37 CFR 1.97 and 1.98.
12. ☐ An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.28 and 3.31 is included.
13. ☒ A **FIRST** preliminary amendment.
14. ☐ A **SECOND** or **SUBSEQUENT** preliminary amendment.
15. ☒ A substitute specification.
16. ☐ A change of power of attorney and/or address letter.
17. ☐ A computer-readable form of the sequence listing in accordance with PCT Rule 13ter.2 and 35 U.S.C. 1.821 - 1.825.
18. ☐ A second copy of the published international application under 35 U.S.C. 154(d)(4).
19. ☐ A second copy of the English language translation of the international application under 35 U.S.C. 154(d)(4).
20. ☐ Other items or information:

U.S. APPLICATION NO. (if known, 37 CFR 1.1)		INTERNATIONAL APPLICATION NO.		ATTORNEY'S DOCKET NUMBER	
10/030020		PCT/EP00/05703		077306.0101	

21. <input checked="" type="checkbox"/> The following fees are submitted: BASIC NATIONAL FEE (37 CFR 1.492 (a) (1) - (5)): Neither international preliminary examination fee (37 CFR 1.482) nor international search fee (37 CFR 1.445(a)(2)) paid to USPTO and International Search Report not prepared by the EPO or JPO..... \$1040.00 International preliminary examination fee (37 CFR 1.482) not paid to USPTO but International Search Report prepared by the EPO or JPO \$890.00 International preliminary examination fee (37 CFR 1.482) not paid to USPTO but international search fee (37 CFR 1.445(a)(2)) paid to USPTO \$740.00 International preliminary examination fee (37 CFR 1.482) paid to USPTO but all claims did not satisfy provisions of PCT Article 33(1)-(4) \$710.00 International preliminary examination fee (37 CFR 1.482) paid to USPTO and all claims satisfied provisions of PCT Article 33(1)-(4) \$100.00 ENTER APPROPRIATE BASIC FEE AMOUNT =				CALCULATIONS PTO USE ONLY	
				\$ 890.00	
Surcharge of \$130.00 for furnishing the oath or declaration later than <input type="checkbox"/> 20 <input type="checkbox"/> 30 months from the earliest claimed priority date (37 CFR 1.492(e)).				\$	
CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE	\$	
Total claims	- 20 =		x \$18.00	\$	
Independent claims	- 3 =		x \$84.00	\$	
MULTIPLE DEPENDENT CLAIM(S) (if applicable)			+ \$280.00	\$	
TOTAL OF ABOVE CALCULATIONS =				\$ 890.00	
<input checked="" type="checkbox"/> Applicant claims small entity status. See 37 CFR 1.27. The fees indicated above are reduced by 1/2.				\$ 445.00	
SUBTOTAL =				\$ 445.00	
Processing fee of \$130.00 for furnishing the English translation later than <input type="checkbox"/> 20 <input type="checkbox"/> 30 months from the earliest claimed priority date (37 CFR 1.492(f)).				\$	
TOTAL NATIONAL FEE =				\$ 445.00	
Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31). \$40.00 per property +				\$	
TOTAL FEES ENCLOSED =				\$ 445.00	
				Amount to be refunded:	\$
				charged:	\$

a. ☒ A check in the amount of \$ 445.00 to cover the above fees is enclosed.


b. ☐ Please charge my Deposit Account No. _____ in the amount of \$ _____ to cover the above fees.
A duplicate copy of this sheet is enclosed.

c. ☒ The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any
overpayment to Deposit Account No. 02-0383. A duplicate copy of this sheet is enclosed.

d. ☐ Fees are to be charged to a credit card. **WARNING:** Information on this form may become public. **Credit card
information should not be included on this form.** Provide credit card information and authorization on PTO-2038.

NOTE: Where an appropriate time limit under 37 CFR 1.494 or 1.495 has not been met, a petition to revive (37 CFR
1.137 (a) or (b)) must be filed and granted to restore the application to pending status.

SEND ALL CORRESPONDENCE TO:


 SIGNATURE
 Bruce W. Slayden, II
 NAME
 33,790
 REGISTRATION NUMBER

531 Rec'd PCT

26 DEC 2001

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant : Gerking, Lüder

Serial No. : Unassigned Examiner: Unassigned

Filed : June 24, 1999 Group Art Unit: Unassigned

For : *Method and Device for the Production of an Essentially Continuous Fine Thread*

PRELIMINARY AMENDMENT

I hereby certify that this paper or fee is being deposited with the United States Postal Service "EXPRESS MAIL POST OFFICE TO ADDRESSEE" Service under 37 CFR 1.10 on the date indicated above and is addressed to the Commissioner for Patents, U. S. Patent and Trademark Office, Washington, D.C. 20231.

December 21, 2001

Date of Deposit

Bruce W. Slayden, II

Attorney Name

Signature

33,790

PTO Registration No.

EL865848296US

Express Mail Label No.

Box Non-Fee Amendments
U. S. Patent and Trademark Office
Washington, D.C. 20231

Sir:

Prior to calculating the fee and examining the above identified patent application,
please amend the application as follows:

In the Claims:

The following is the clean version of all pending claims of the present application under 37 C.F.R. 1.121(c)(3) and preprinted here for the convenience of the Examiner.

1. Method for the manufacture of essentially endless fine threads from meltable polymers, in which polymer melt is spun from at least one spin hole and passed through a Laval nozzle, wherein the spun thread is drawn by gas streams accelerated to high speed by means of the Laval nozzle, and wherein with a given geometry of the melt hole and its position relative to the Laval nozzle the temperature of the polymer melt, its throughput per spin hole and the pressures in front of and behind the Laval nozzle which define the speed of the gas streams are controlled in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.
2. (AMENDED) Method according to claim 1, wherein the gas flow around the at least one thread is laminar.
3. (AMENDED) Method according to claim 1, wherein the space behind the Laval nozzle is at ambient pressure or, in case of further processing of the threads, is at a pressure slightly above ambient pressure, which is necessary for further processing.
4. (AMENDED) Method according to claim 1, wherein the gas streams which draw the thread are at ambient temperature or a temperature caused by their supply.
5. (AMENDED) Method according to claim 1, wherein the ratio of the pressures in the space above and below the Laval nozzle when using air is selected between 1.02 and 2.5, depending on the polymer, its throughput and melting temperature.
6. (AMENDED) Method according to claim 1, wherein the thread emerging from the spin hole is heated by radiation in the region of the Laval nozzle.
7. (AMENDED) Method according to claim 1, wherein a plurality of threads are spun and split, which are deposited to form a non-woven fabric of further processed into yarns.

8. (AMENDED) Apparatus with a spinning head connected to a feeder for the melt, a spinning nozzle assembly which is held in the spinning head and comprises at least one spin hole and which spins a melt monofilament, a plate (6') which is located below the spinning head (11) and which comprises a Laval nozzle (6) arranged in a fixed geometrical relationship to the spin hole (4), wherein between plate (6') and spinning head (11) is formed a closed first space (8) provided with a supply of gas (5) and below the plate (6') is provided a second space (7), and wherein the throughput of the melt per spin hole (4), the temperature of the melt and the pressure in the first and second spaces are adjusted in such a way that the spun melt monofilament carried by the flow of gas after leaving the Laval nozzle (6) before solidification thereof attains a hydrostatic pressure which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.
9. (AMENDED) Apparatus according to claim 8, wherein the spinning assembly (3) is insulated from the first space (8) in the region of the at least one spin hole (4) by an insulating assembly (9) and/or is heated in the region of the at least one spin hole (4).
10. (AMENDED) Apparatus according to claim 8 wherein the pressure ratios in the first and second spaces (8, 7) are adjusted in such a way that the gas flow in the Laval nozzle (6) attains speeds up to the speed of sound and over.
11. (AMENDED) Apparatus according to claim 8, wherein the second space (7) is at ambient pressure or a few mbar over.
12. (AMENDED) Apparatus according to claim 8, wherein the supplied gas is at ambient temperature or the temperature of its feeder.
13. (AMENDED) Apparatus according to claim 8, wherein the outlet opening of the at least one spin hole (4) in the region of the Laval nozzle (6) is located at the level of the upper edge of the plate (6'), a few mm above the upper edge of the plate, or extends a few mm into the Laval nozzle (6).

14. (AMENDED) Apparatus according to claim 8, wherein the spinning nozzle assembly comprises a plurality of spin holes (4) which are if occasion arises provided with nipples and which form a row or several parallel rows.
15. (AMENDED) Apparatus according to claim 8, wherein the plate comprises at least one elongate Laval nozzle.
16. (AMENDED) Apparatus according to claim 8, wherein the plate comprises a plurality of rotationally symmetrical Laval nozzles.
17. (AMENDED) Apparatus according to claim 8, wherein a delivery belt is provided for deposition of the threads and formation of a non-woven fabric.
18. (AMENDED) Apparatus according to claim 8, wherein a winding device is provided for winding the threads.

19. (AMENDED) Non-woven fabric made from threads manufactured from meltable polymers, in which polymer melt is spun from at least one spin hole and passed through a Laval nozzle, wherein the spun thread is drawn by gas streams accelerated to high speed by means of the Laval nozzle, and wherein with a given geometry of the melt hole and its position relative to the Laval nozzle the temperature of the polymer melt, its throughput per spin hole and the pressures in front of and behind the Laval nozzle which define the speed of the gas streams are controlled in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.
20. (AMENDED) Yarns made from threads which have been produced from meltable polymers, in which polymer melt is spun from at least one spin hole and passed through a Laval nozzle, wherein the spun thread is drawn by gas streams accelerated to high speed by means of the Laval nozzle, and wherein with a given geometry of the melt hole and its position relative to the Laval nozzle the temperature of the polymer melt, its throughput per spin hole and the pressures in front of and behind the Laval nozzle which define the speed of the gas streams are controlled in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.

The following are the marked up version of the claims indicating precisely where the amendments were made:

2. (AMENDED) Method according to claim 1, **[characterised in that]wherein** the gas flow around the at least one thread is laminar.
3. (AMENDED) Method according to claim 1 **[or claim 2, characterised in that]wherein** the space behind the Laval nozzle is at ambient pressure or, in case of further processing of the threads, is at a pressure slightly above ambient pressure, which is necessary for further processing.
4. (AMENDED) Method according to claim 1, **[any of claims 1 to 3, characterised in that]wherein** the gas streams which draw the thread are at ambient temperature or a temperature caused by their supply.
5. (AMENDED) Method according to claim 1, **[any of claims 1 to 4, characterised in that]wherein** the ratio of the pressures in the space above and below the Laval nozzle when using air is selected between 1.02 and 2.5, depending on the polymer, its throughput and melting temperature.
6. (AMENDED) Method according to claim 1, **[any of claims 1 to 5, characterised in that]wherein** the thread emerging from the spin hole is heated by radiation in the region of the Laval nozzle.
7. (AMENDED) Method according to claim 1, **[any of claims 1 to 6, characterised in that]wherein** a plurality of threads are spun and split, which are deposited to form a non-woven fabric of further processed into yarns.
8. (AMENDED) Apparatus **[for carrying out the method according to any of claims 1 to 7]** with a spinning head connected to a feeder for the melt, a spinning nozzle assembly which is held in the spinning head and comprises at least one spin hole and which spins a melt monofilament, a plate (6') which is located below the spinning head (11) and which comprises a Laval nozzle (6) arranged in a fixed geometrical relationship to the spin hole

(4), wherein between plate (6') and spinning head (11) is formed a closed first space (8) provided with a supply of gas (5) and below the plate (6') is provided a second space (7), and wherein the throughput of the melt per spin hole (4), the temperature of the melt and the pressure in the first and second spaces are adjusted in such a way that the spun melt monofilament carried by the flow of gas after leaving the Laval nozzle (6) before solidification thereof attains a hydrostatic pressure which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.

9. (AMENDED) Apparatus according to claim 8, **[characterised in that]wherein** the spinning assembly (3) is insulated from the first space (8) in the region of the at least one spin hole (4) by an insulating assembly (9) and/or is heated in the region of the at least one spin hole (4).
10. (AMENDED) Apparatus according to claim 8 **[or 9, characterised in that]wherein** the pressure ratios in the first and second spaces (8, 7) are adjusted in such a way that the gas flow in the Laval nozzle (6) attains speeds up to the speed of sound and over.
11. (AMENDED) Apparatus according to **claim 8**, **[any of claims 8 to 10, characterised in that]wherein** the second space (7) is at ambient pressure or a few mbar over.
12. (AMENDED) Apparatus according to **claim 8**, **[any of claims 8 to 11, [characterised in that]wherein** the supplied gas is at ambient temperature or the temperature of its feeder.
13. (AMENDED) Apparatus according to **claim 8**, **[any of claims 8 to 12, characterised in that]wherein** the outlet opening of the at least one spin hole (4) in the region of the Laval nozzle (6) is located at the level of the upper edge of the plate (6'), a few mm above the upper edge of the plate, or extends a few mm into the Laval nozzle (6).
14. (AMENDED) Apparatus according to **claim 8**, **[any of claims 8 to 13, characterised in that]wherein** the spinning nozzle assembly comprises a plurality of spin holes (4) which are if occasion arises provided with nipples and which form a row or several parallel rows.

15. (AMENDED) Apparatus according to claim 8, [any of claims 8 to 14, characterised in that]wherein the plate comprises at least one elongate Laval nozzle.
16. (AMENDED) Apparatus according to claim 8, [any of claims 8 to 14, characterised in that]wherein the plate comprises a plurality of rotationally symmetrical Laval nozzles.
17. (AMENDED) Apparatus according to claim 8, [any of claims 8 to 16, characterised in that]wherein a delivery belt is provided for deposition of the threads and formation of a non-woven fabric.
18. (AMENDED) Apparatus according to claim 8, [any of claims 8 to 16, characterised in that]wherein a winding device is provided for winding the threads.
19. (AMENDED) Non-woven fabric made from threads [which have been produced by the method according to any of claims 1 to 7] manufactured from meltable polymers, in which polymer melt is spun from at least one spin hole and passed through a Laval nozzle, wherein the spun thread is drawn by gas streams accelerated to high speed by means of the Laval nozzle, and wherein with a given geometry of the melt hole and its position relative to the Laval nozzle the temperature of the polymer melt, its throughput per spin hole and the pressures in front of and behind the Laval nozzle which define the speed of the gas streams are controlled in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.
20. (AMENDED) Yarns made from threads which have been produced [by the method according to any of claims 1 to 7]from meltable polymers, in which polymer melt is spun from at least one spin hole and passed through a Laval nozzle, wherein the spun thread is drawn by gas streams accelerated to high speed by means of the Laval nozzle, and wherein with a given geometry of the melt hole and its position relative to the Laval nozzle the temperature of the polymer melt, its throughput per spin hole and the pressures in front of and behind the Laval nozzle which define the speed of the gas streams are controlled in such a way that the thread before

solidification thereof attains a hydrostatic pressure in its interior which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.

Please add the following abstract:


Abstract

The invention relates to a method and a device for the production of essentially continuous fine threads made of meltable polymers. The polymer melt is spun from at least one spin hole (5) and the spun thread is twisted using gas flows which are accelerated to achieve high speeds by means of a Laval nozzle (6). As a result of the specific geometry of the melt hole (4) and the position thereof in respect to the Laval nozzle (6), the temperature of the polymer melt, the throughput per spin hole and the pressures determining the velocity of the gas flow upstream and downstream from the Laval nozzle (6) are controlled in such a way that the thread reaches an internal hydrostatic pressure before solidifying, whereby said thread bursts into a plurality of fine threads.

In the specification:

For the convenience of the Examiner, a substitute specification is provided under 37 C.F.R. 1.125. A marked up version based on the English translation is also provided according to 37 C.F.R. 1.125.

Respectfully submitted,

A handwritten signature in black ink, appearing to read "Bruce W. Slayden, II", is written over a horizontal line.

Bruce W. Slayden, II

Reg. No. 33,790

Baker Botts L.L.P.

One Shell Plaza

910 Louisiana Street

Houston, TX 77002-4995

Telephone: (713) 229-1786

Facsimile: (713) 229-7886

ATTORNEY FOR APPLICANT

Date: December 21, 2001

Clean Version of Amendments to Specification**Method and Device for the Production of An Essentially Continuous Fine Thread****FIELD OF THE INVENTION**

The invention concerns a method for the manufacture of very fine threads from melt-spinnable polymers and an apparatus for the manufacture thereof.

BACKGROUND OF THE RELATED TECHNOLOGY

Microthreads of this kind, but usually microfibres of finite length, have for many years been made by a hot-air spun-blown method, the so-called melt-blown method, and today there are different apparatuses for this. A common feature of all of them is that, in addition to a row of melt holes – several rows parallel to each other have also become known – hot air which draws the threads escapes. By mixing with the colder ambient air, there is cooling and solidification of these threads or fibres, for often, usually of course undesirably, the threads break. The disadvantage of this melt-blown method is the high expenditure of energy to heat the hot air flowing at high speed, a limited throughput through the individual spin holes (even though these have been set increasingly closer together in the course of time, down to a spacing of below 0.6 mm with 0.25 mm in hole diameter), that with thread diameters of less than 3 μm breaks occur, which leads to beads and protruding fibres in the subsequent textile composite, and that due to the high air temperature necessary to produce fine threads the polymers are thermally damaged well above the melt temperature. The spinning nozzles, of which a large number have been proposed and also protected, are elaborate injection moulding dies which have to be made with high precision. They are expensive, operationally susceptible and tedious to clean.

SUMMARY OF THE INVENTION

It is therefore the object of the present invention to provide a method and an apparatus for the manufacture of essentially endless threads, which require less expenditure of energy, do not cause thread damage on account of excessive temperatures and use a spinning tool of simple construction.

This object is achieved according to the invention by the characteristics of the independent claims.

The present invention avoids the disadvantages of the state of the art by the fact that polymer melt is pressed out of spin holes, which are arranged in one or more parallel rows or rings, into a chamber having a given pressure which is filled with gas, as a rule with air, and which is separate from the environment, wherein in the molten state the threads pass into a region with rapid acceleration of this gas at the outlet from the chamber. The forces transmitted to the respective thread on the way there by shear stress increase, its diameter decreases greatly and the pressure in its still liquid interior increases to a corresponding extent in inverse proportion to its radius due to the effect of the surface tension. Due to the acceleration of the gas, its pressure drops by the laws of flow mechanics. In the process, the conditions of the melt temperature, gas flow and its rapid acceleration are coordinated with each other in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the surrounding gas pressure, so that the thread bursts and divides into a plurality of fine threads. Due to a gap at the bottom in the chamber, threads and air leave the latter. Bursting takes place after the gap and under otherwise unchanged conditions with surprising stability at a given fixed location. In the region of great acceleration, gas and thread streams run parallel, the flow interface around the threads being laminar. Continued splitting of the original thread monofilament occurs without bead formation and breaks. From a monofilament is produced a multifilament of very much finer threads using a gas stream having ambient temperature or gas stream slightly above this.

The new threads arising from splitting are considerably finer than the original monofilament. They may even still be drawn slightly after the splitting point until they are solidified. This happens very quickly because of the greater thread area suddenly created. The threads are endless. But more to a minor extent they can be threads of finite length due to deviations in the polymer, individual speed or temperature disturbances, dust in the gas and the like disturbances in real industrial processes. The process of splitting thread-forming polymers can be adjusted in such a way that the numerous very much finer single filaments produced from the monofilament are endless. The threads have a diameter of well below 10 μm , mainly between 1.5 and 5 μm ,

which in the case of polymers corresponds to a titre of between about 0.02 and 0.2 dtex, and are referred to as microthreads.

The area of great acceleration and pressure drop in the gas stream is according to the invention realised in the form of a Laval nozzle with convergent contour to a narrowest cross-section and then rapid widening, the latter already so that the newly formed single threads running adjacent to each other cannot stick to the walls. In the narrowest cross-section, with a suitable choice of pressure in the chamber (in the case of air, about twice as high as the ambient pressure behind), the speed of sound can prevail, and in the wider portion of the Laval nozzle supersonic speed prevails.

For the manufacture of non-woven thread fabrics (spun-bonded fabrics), spinning nozzles in row form and Laval nozzles of rectangular cross-section are used. For the manufacture of yarns and for special kinds of non-woven fabric manufacture, round nozzles with one or more spin holes and rotationally symmetrical Laval nozzles can also be used.

The method borrows from methods for the manufacture of metal powders from melts, from which it was developed. According to DE 33 11 343, the molten metal monofilament in the region of the narrowest cross-section of a Laval nozzle bursts into a large number of particles which are deformed into pellets by the surface tension and cooled down. Here too the result is a liquid pressure in the interior of the melt monofilament which outweighs the surrounding laminar gas flow. If the pressure drop takes place so rapidly that solidification is not yet close, the pressure forces can outweigh the forces of cohesion of the molten mass, mainly viscosity forces, and bursting into a plurality of filament pieces (ligaments) occurs. The crucial factor here is that the thread must remain liquid at least in the interior so that this mechanism can set in. It has therefore also been proposed to further heat the monofilament after its emergence from the spinning nozzle.

Automatic bursting of a molten metal thread is also named the "NANOVAL effect" after the firm which uses it.

Defibration by bursting has become known in the manufacture of mineral fibres, thus in DE-A-33 05 810. By interfering with the gas flow in a rectangular channel arranged below the spinning nozzle by means of fittings which generate cross flows, as stated there the result is defibration of the single melt monofilament. In a not quite clear account there is mention of defibration by static pressure gradient in the air flow, and in fact in EP 0 038 989 drawing from a 'loop or zigzag movement ... after the fashion of a multiple whiplash effect'. The fact that the actual 'defibration' is caused by an increase in pressure in the interior of the thread and decrease in the surrounding gas flow was not recognised, nor any control mechanisms in this direction.

For polymers, this finding from mineral fibre manufacture was obviously made use of by the same applicant firm. In DE-A-38 10 596 in an apparatus according to Fig. 3 and description in example 4 the melt stream of polyphenylene sulphide (PPS) is 'defibrated by a high static pressure gradient'. The gas streams are hot, even heated beyond the melting point of the PPS. A static pressure gradient in the gas flow, decreasing in the direction of thread travel, cannot on its own defibrate the thread. It was not recognised that, for this, the melt stream must remain liquid in its interior, at least in an adequate portion. But by using hot air in the region of the polymer melt temperature, this happens by itself. It is not a 'pressure gradient occurring after the outlet holes', column 1, lines 54-55 that draws the melt streams into fine fibres, but a static pressure gradient between melt stream and surrounding gas flow that causes it to split or defibrate. The threads produced are of finite length and amorphous.

The threads of the method according to the invention on the other hand are endless or essentially endless. They are produced by selectively controlled bursting of a still molten monofilament in a laminar gas flow surrounding them, that is, without turbulence-generating cross flows. Basically all thread-forming polymers are considered, such as polyolefins PP, PE, polyester PET, PBT, polyamides PA 6 and PA 66 and others such as polystyrene. Here, those such as polypropylene (PP) and polyethylene (PE) are to be regarded as favourable because surface tension and viscosity are in a ratio which readily allows the build-up of an internal thread pressure against the surface tension force of the thread skin, while the viscosity is not so high that bursting is prevented. The ratio of surface tension to viscosity can be increased by increasing the melt temperature in most polymers. This takes place in a simple manner in melt manufacture and can

be reinforced by heating the spinning nozzles shortly before emergence of the threads. Heating the threads afterwards by hot gas streams does not however take place according to the present invention.

It can be established that the subject of the invention, controlled splitting of a polymer thread drawn with cold air into a plurality of finer single threads of endless or essentially endless single threads, has not yet been found. This takes place by the automatic effect of bursting of the melt thread due to a positive pressure difference between the hydraulic pressure in the thread, arising from the surface tension of the thread envelope, and the gas flow surrounding it. If the pressure difference is so great that the strength of the thread envelope is no longer sufficient to hold together the interior, then the thread bursts. Splitting into a plurality of finer threads occurs. The gas, usually air, can be cold, i.e. does not have to be heated, only the process conditions and the apparatus must be such that the melt monofilament in its critical diameter which depends on the melt viscosity and the surface tension of the polymer concerned is not cooled to such an extent that it can no longer burst due to the internal liquid pressure building up. Also the melt holes must not be cooled by the gas so greatly that the melt cools down too greatly, let alone already solidifies there. The process and geometrical conditions for producing this splitting effect are relatively easy to find.

The advantage of the present invention lies in that, in a simple and economical manner, very fine threads within a range of well below 10 μm , mainly between 2 and 5 μm , can be produced, which in the case of pure drawing for example by the melt-blow method can be accomplished only with hot gas (air) jets heated above melting point, and so requires considerably more energy. Moreover, the threads are not damaged in their molecular structure by excessive temperatures, which would lead to reduced strength, with the result that they can then often be rubbed out of a textile structure. Another advantage lies in that the threads are endless or quasi-endless and cannot protrude from a textile structure such as a non-woven fabric and come away as fuzz. The apparatus for carrying out the method according to the invention is simple. The spin holes of the spinning nozzle can be larger and so less susceptible to breakdowns, and the Laval nozzle cross-section in its precision does not need the narrow tolerances of the lateral air slots of the melt-blown method. For a given polymer one need only coordinate the melt

temperature and the pressure in the chamber with each other, and with a given throughput per spin hole and the geometrical position of the spin holes relative to the Laval nozzle splitting occurs.

BRIEF DESCRIPTION OF THE DRAWINGS

Practical examples of the invention are shown in the drawings and described in more detail in the description below. They show:

- Fig. 1 a schematic sectional view of an apparatus for the manufacture of microthreads by means of cold gas jets by bursting of a melt stream into a plurality of single threads according to a first embodiment of the invention,
- Fig. 2 a perspective partial view of the apparatus according to the invention in an embodiment with row nozzle and spin holes in nipple form for the manufacture of non-woven fabrics from microthreads, and
- Fig. 3 a partial view in section of the spinning nozzle and Laval nozzle according to a third embodiment of the invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENT

In Fig. 1 is shown an apparatus for the manufacture of essentially endless fine threads from melt-spinnable polymers, which comprises a spinning head or spinning beam 11, not described in more detail, in which is held a spinning nozzle 1. The spinning head 11 and the spinning nozzle are in a generally known manner composed of different parts, so that a description of them is omitted. The spinning head or spinning beam 11 is surrounded by a heating system 12 which is designed as a system for liquid or steam heating via chambers or as an electric band heating system. The spinning head or spinning beam is connected to melt-proportioning devices, not shown, such as spinning pumps and extruders, which are the usual devices for the manufacture of synthetic fibres, so that these are not described further either.

The spinning nozzle comprises a nozzle orifice 3 which comprises one, or usually several spin holes arranged in a row. Several parallel rows are possible too. Below the spinning head 11 is located a plate 6' with a gap 6 which is of convergent-divergent construction and widens greatly due to a space 7 located below it and forms a Laval nozzle. Depending on the shape of the spinning nozzle 1, the Laval nozzle 6 is constructed rotationally symmetrically similarly to a stop in the case of a single nozzle or as a longitudinal gap in the case of a row nozzle. The spinning nozzle or the spin holes of the spinning nozzle end just above the Laval nozzle 6 or in the plane of the plate 6', but the spinning nozzle 1 can also extend slightly into the Laval nozzle 6.

Between spinning head and plate 6' is located a closed chamber 8, to which gas is supplied in the direction of the arrows 5 for example by a compressor. The gas is usually at ambient temperature, but can be at a slightly higher temperature, for example 70 to 80°, on account of the heat of compression from the compressor.

The nozzle orifice 3 is surrounded by an insulating assembly 9 which protects the nozzle orifice 3 against excessive heat losses due to the gas flow 5. In addition an electric band heating system 10 can be arranged between insulating assembly 9 and orifice 3.

The space 7 is usually at ambient pressure, while the gas in the chamber 8 is at an elevated pressure compared with the space 7. In the case of directly following further processing into a non-woven fabric or other thread structures, the space 7 can be at a slightly elevated pressure compared with ambient pressure, i.e. atmospheric pressure, for example a few mbar higher, which is needed for the further processing, such as non-woven fabric laying or other thread collecting devices.

The polymer melt is pressed in the direction of the arrow 2 out of the nozzle orifice 3 out of the spin hole or opening 4 as a melt monofilament, and is picked up by the gas jets 5 and tapered to smaller diameters by shear stresses at its circumference. As the basically cold gas streams, which can be air streams, cool it down, after a few millimetres it must pass into the narrowest region of the Laval nozzle and so into an area of lower pressure. As soon as the taper has progressed so far and due to the effect of the surface tension of the melt at the thread envelope the pressure in the interior has increased so far that it is above that of the gas flow, bursting of

the monofilament occurs, namely when the thread envelope can no longer hold the melt thread together against the internal pressure which has increased with thread constriction. The melt monofilament is divided into single threads which, on account of the temperature difference between melt and cold gas or air and the suddenly greatly increased surface area of the single threads referred to the thread mass, cool down rapidly. Hence a given number of very fine essentially endless single threads is produced.

It follows from the nature of such bursting processes similar to explosions that the number of threads produced after the splitting point, which can be for example 5 to 25 mm below Laval nozzle 6, cannot be constant. Because of the short distance which thread and gas together cover up to the splitting point, the flow interface around the thread is laminar. Preferably also the air from the supply pipes is conducted in laminar fashion as far as possible to the region of splitting. This has the advantage of the lower flow losses and hence the lower energy requirements which distinguish laminar flows compared with turbulent ones, but also a more uniform time curve of splitting, because disturbances due to turbulent changes are absent. The accelerated flow such as is present in the cross-section of the Laval nozzle 6 remains laminar and can even be laminarised if a certain turbulence prevailed before.

The added advantage of laminar drawing of the melt monofilament up to the splitting point and also beyond it leads to splitting into more uniform single threads, because there are not greater differences in the flow rate and hence in the sheer stress acting on the melt monofilament and resulting single threads and in the pressure of gas flow. The distribution of the thread diameters is, as it turned out surprisingly, very narrow, e.g. propylene threads whose diameters are all between 2 and 4 μm can be produced.

As already stated above, the speed of gas flow in the direction of the arrows 5 increases constantly towards the spin hole 4 and then in the Laval nozzle 6. In the narrowest cross-section of the Laval nozzle it can increase up to the speed of sound if the critical pressure ratio, depending on the gas, is reached, and in the case of air the ratio between the pressure in the chamber 8 and the space 7 is around 1.9.

The threads move downwards in the direction of the arrows 21 and for example can be deposited on a belt, not shown, to form a non-woven fabric, or otherwise further treated.

In Fig. 2 is shown a further example of the present invention, in which the spinning nozzle 1 is constructed as a row nozzle. Here are shown in particular the outlet points of the spinning nozzle 1 with orifice 3 which comprises nipples 25. This form allows concentric access of the gas to the melt monofilament, which proved to be advantageous for splitting, both with respect to the obtainable fineness of the threads and with respect to the width of fluctuation of their diameters.

By contrast with the band heating system 10 according to Fig. 1, here round heating elements 26 are shown for the supply of heat to the nozzle orifice 3 which is shielded by insulators 27 from the gas flow 5. The threads leave the Laval nozzle in a wide curtain together with the gas, and move in the direction of the arrows 21 towards a collecting belt 20 and are deposited in the region 22 to form a non-woven fabric 23. The non-woven fabric 23 leaves the area of its manufacture in the direction of arrow 24.

A further embodiment of the spinning and splitting apparatus according to the invention is shown in Fig. 3. Here again the melt monofilament is expelled from an insulated nozzle orifice 3 with one or more melt holes 4 and picked up by the laterally applied gas stream 5 and drawn in length into thinner diameters by shear stress forces. In the plate 6' in the region of the Laval nozzle 6 a heating device 30 is incorporated. On the way to the narrowest cross-section of the Laval nozzle 6, therefore, the melt monofilament has heat supplied to it by radiation. As a result, cooling by the basically cold air/gas streams is delayed. The melt monofilament passes, drawn to a smaller diameter, into the partial-pressure area of the Laval nozzle 6 and can split into even finer single threads.

The following examples describe methods and apparatuses with the essential process data used with different raw materials and the thread results.

Example 1

By means of a laboratory extruder (screw with a diameter of 19 mm and $L/D = 25$) for the processing of polymers, polypropylene (PP) with a MFI (melt flow index) of 25 (230°C , 2.16 kg)

was melted and supplied via a gear spinning pump to a spinning head with a nozzle orifice 3 comprising seven holes 4 arranged in a row at equal intervals of 4.5 mm each, with a diameter of the holes 4 of 1 mm. The melt-conducting pipes were heated from the outside by electric band heating systems. The nozzle orifice 3 was insulated according to Fig. 1 at its flanks by a ceramic insulator 9 (calcium silicate) against the gas flow below it and heated with electric heating systems. Below the spinning nozzle 1 was located the chamber 8 for gas supply. Air which was taken from a compressed air network and fed into the latter by a compressor was taken as the gas in this and the other examples. The chamber 8 was defined at the bottom by a plate which had a slot forming the Laval nozzle 6 with a width of 4 mm at its narrowest cross-section. The lateral supply cross-sections for the air in the chamber had a height of 32 mm, measured from the upper edge of the Laval nozzle plate 6'. The outlet openings of the holes 4 were arranged exactly at the level of the upper edge of the Laval nozzle plate 6' and had a distance of 10 mm from the narrowest cross-section of the Laval nozzle 6.

Melt pressure and temperature between spinning pump and connecting piece to the spinning nozzle 1 were measured with a strain-gauge pressure measuring device (Dynisco, model MDA 460) or a thermoelement.

Characterisation of the threads obtained is by the thread diameter d_{50} averaged over 20 single measurements, and if required also by the standard deviation s .

Splitting is characterised by the theoretical thread count N . This indicates how many single filaments of the measured average thread diameter d_{50} must move at the maximum possible speed through the narrowest cross-section of the Laval nozzle 6 in order to convert the measured melt mass to single filaments. The maximum possible speed is the gas speed in the narrowest cross-section of the Laval nozzle 6, which is either the speed of sound which can be calculated from the conditions in the chamber 8 or, in the event that the critical pressure ratio which is needed to attain the speed of sound is not attained, can be calculated from these conditions with Saint-Venant and Wantzell's formula. If the theoretical thread count N is more than 1, the thread diameter observed cannot have been produced simply by drawing, this would be contrary to the law of preservation of mass. For the observed theoretical thread counts N well over 1, only splitting is possible as an explanation. A multiple whiplash effect can perhaps explain values

just over 1 to 10, but not the observed values of up to 627. As the actual thread speed must be below the maximum, the single filament number actually obtained will be above the theoretical number.

At a melt temperature of 340°C and a melt pressure between spinning pump and connecting piece to the spinning nozzle 1 of approximately 1 bar above the pressure in the pressure 8, which was approximately also the pressure in front of the spinning capillaries, and with a quantity proportioned via the spinning pump of 43.1 g/min, that is, 6.2 g/min per hole, the following thread values resulted at the different pressures in the chamber 8 above the atmospheric pressure in space 7:

0.25 bar	$d_{50} = 7.6 \text{ } \mu\text{m}$, $N = 123$
0.5 bar	$d_{50} = 4.4 \text{ } \mu\text{m}$, $N = 276$
1.0 bar	$d_{50} = 3.9 \text{ } \mu\text{m}$, $N = 283$

If only 4.6 g/min are passed through instead of 6.2 g/min per hole, at a pressure in the chamber 8 of 0.5 bar a d_{50} of 3.0 μm instead of 4.4 μm is obtained.

How important exact coordination of melt temperature, melt quantity and gas flow is, is shown by the following example of a distance between the holes 4 of 15 mm, a throughput per hole 4 of 4.6 g/min and a pressure in the chamber 8 of 0.5 bar:

melt temperature 340°C	$d_{50} = 3.0 \text{ } \mu\text{m}$, $s = 0.8 \text{ } \mu\text{m}$, $N = 187$
melt temperature 305°C	$d_{50} = 8.2 \text{ } \mu\text{m}$, $s = 4.7 \text{ } \mu\text{m}$, $N = 25$.

Clearly conditions are such that around the monofilaments there has already formed a cold envelope which greatly hinders splitting. Not the whole monofilament is split open, but only a portion, which can be seen by the fact that, although the minimum observed thread diameter has not changed (some therefore split open), some single filaments with a diameter of more than 10 μm occur. Thus no splitting has occurred there. At the higher temperature, on the other hand, all single filaments are between 1.6 μm and 4.8 μm . The greater variance of thread diameters is reflected in the much greater standard deviation.

A design of the orifice 3 with nipples 25 according to Fig. 2 allows the manufacture of much finer threads with a smaller width of fluctuation and/or a distinct increase in throughput. Thus, for a temperature of 370°C, a distance between holes 4 of 15 mm, a distance from outlet openings of the holes 4 to the narrowest cross-section of the Laval nozzle of 8.5 mm (the outlet openings are submerged 1.5 mm in the imaginary plane of the Laval nozzle plate) and a pressure in the chamber 8 of 0.75 bar, the following thread values are obtained:

6.2 g/min per hole $d_{50} = 2.1 \mu\text{m}$, $s = 0.30 \mu\text{m}$, $N = 445$

12.3 g/min per hole $d_{50} = 2.5 \mu\text{m}$, $s = 0.60 \mu\text{m}$, $N = 627$

Example 2

With the apparatus from example 1, polyamide 6 (PA6) with a relative viscosity $\eta_{\text{rel}} = 2.4$ was fed to a nozzle orifice 3 with 58 holes 4 at intervals of 1.5 mm and with a diameter of 0.4 mm. The distance from the outlet openings of the holes 4 to the narrowest cross-section of the Laval nozzle was 12.0 mm (the outlet openings ended 2.0 mm above the imaginary plane of the Laval nozzle plate). With a throughput per hole 4 of 0.25 g/min and a pressure in the chamber 8 of 0.02 bar above the environment, filaments with a mean diameter d_{50} of 4.1 μm were produced.

Example 3

With the apparatus from example 1, polypropylene (PP) with a MFI of 25 (230°C, 2.16 kg) was fed to a nozzle orifice 3 with three holes 4 at intervals of 15 mm and with a diameter of 1.0 mm. Individual rotationally symmetrical Laval nozzles 6 were arranged in the Laval nozzle plate 3 coaxially with the three holes 4. The outlet openings of the holes 4 were arranged exactly at the level of the upper edge of the Laval nozzle plate and had a distance of 4.5 mm from the narrowest cross-section of the Laval nozzles 6. At a pressure in the chamber 8 of 0.75 bar above the environment 7 and with a throughput per hole 4 of 9.3 g/min, single filaments with a mean diameter d_{50} of 4.9 μm were produced. In this case a theoretical thread count of 123 results.

Of interest in this manner of operation is the observation that the bursting point compared with example 1 has clearly shifted in the direction of the narrowest cross-section of the Laval nozzles 6. Whereas in the case of the slot-like Laval nozzle 6 this point is about 25 mm below the narrowest cross-section, the distance in the case of the rotationally symmetrical Laval nozzle 6 is

only about 5 mm. The observation is explained by the fact that, due to the rotationally symmetrical enclosure of the melt thread, higher shear stresses were transmitted to it, and therefore it is drawn more rapidly to the smaller diameter yielding the bursting point. Moreover, the pressure in the free jet after leaving the Laval nozzle 6 does not drop suddenly to the ambient pressure, but only after a certain running length. The free jet characteristics are however in the planar case different to those in the rotationally symmetrical case.

Translation of German Specification

Method and Device for the Production of An Essentially Continuous Fine Thread

The invention concerns a method for the manufacture of very fine threads from melt-spinnable polymers and an apparatus for the manufacture thereof.

Microthreads of this kind, but usually microfibres of finite length, have for many years been made by a hot-air spun-blown method, the so-called melt-blown method, and today there are different apparatuses for this. A common feature of all of them is that, in addition to a row of melt holes – several rows parallel to each other have also become known – hot air which draws the threads escapes. By mixing with the colder ambient air, there is cooling and solidification of these threads or fibres, for often, usually of course undesirably, the threads break. The disadvantage of this melt-blown method is the high expenditure of energy to heat the hot air flowing at high speed, a limited throughput through the individual spin holes (even though these have been set increasingly closer together in the course of time, down to a spacing of below 0.6 mm with 0.25 mm in hole diameter), that with thread diameters of less than 3 μm breaks occur, which leads to beads and protruding fibres in the subsequent textile composite, and that due to the high air temperature necessary to produce fine threads the polymers are thermally damaged well above the melt temperature. The spinning nozzles, of which a large number have been proposed and also protected, are elaborate injection moulding dies which have to be made with high precision. They are expensive, operationally susceptible and tedious to clean.

It is therefore the object of the present invention to provide a method and an apparatus for the manufacture of essentially endless threads, which require less expenditure of energy, do not cause thread damage on account of excessive temperatures and use a spinning tool of simple construction.

This object is achieved according to the invention by the characteristics of the independent claims.

The present invention avoids the disadvantages of the state of the art by the fact that polymer melt is pressed out of spin holes, which are arranged in one or more parallel rows or rings, into a

chamber having a given pressure which is filled with gas, as a rule with air, and which is separate from the environment, wherein in the molten state the threads pass into a region with rapid acceleration of this gas at the outlet from the chamber. The forces transmitted to the respective thread on the way there by shear stress increase, its diameter decreases greatly and the pressure in its still liquid interior increases to a corresponding extent in inverse proportion to its radius due to the effect of the surface tension. Due to the acceleration of the gas, its pressure drops by the laws of flow mechanics. In the process, the conditions of the melt temperature, gas flow and its rapid acceleration are coordinated with each other in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the surrounding gas pressure, so that the thread bursts and divides into a plurality of fine threads. Due to a gap at the bottom in the chamber, threads and air leave the latter. Bursting takes place after the gap and under otherwise unchanged conditions with surprising stability at a given fixed location. In the region of great acceleration, gas and thread streams run parallel, the flow interface around the threads being laminar. Continued splitting of the original thread monofilament occurs without bead formation and breaks. From a monofilament is produced a multifilament of very much finer threads using a gas stream having ambient temperature or gas stream slightly above this.

The new threads arising from splitting are considerably finer than the original monofilament. They may even still be drawn slightly after the splitting point until they are solidified. This happens very quickly because of the greater thread area suddenly created. The threads are endless. But more to a minor extent they can be threads of finite length due to deviations in the polymer, individual speed or temperature disturbances, dust in the gas and the like disturbances in real industrial processes. The process of splitting thread-forming polymers can be adjusted in such a way that the numerous very much finer single filaments produced from the monofilament are endless. The threads have a diameter of well below 10 μm , mainly between 1.5 and 5 μm , which in the case of polymers corresponds to a titre of between about 0.02 and 0.2 dtex, and are referred to as microthreads.

The area of great acceleration and pressure drop in the gas stream is according to the invention realised in the form of a Laval nozzle with convergent contour to a narrowest cross-section and

then rapid widening, the latter already so that the newly formed single threads running adjacent to each other cannot stick to the walls. In the narrowest cross-section, with a suitable choice of pressure in the chamber (in the case of air, about twice as high as the ambient pressure behind), the speed of sound can prevail, and in the wider portion of the Laval nozzle supersonic speed prevails.

For the manufacture of non-woven thread fabrics (spun-bonded fabrics), spinning nozzles in row form and Laval nozzles of rectangular cross-section are used. For the manufacture of yarns and for special kinds of non-woven fabric manufacture, round nozzles with one or more spin holes and rotationally symmetrical Laval nozzles can also be used.

The method borrows from methods for the manufacture of metal powders from melts, from which it was developed. According to DE 33 11 343, the molten metal monofilament in the region of the narrowest cross-section of a Laval nozzle bursts into a large number of particles which are deformed into pellets by the surface tension and cooled down. Here too the result is a liquid pressure in the interior of the melt monofilament which outweighs the surrounding laminar gas flow. If the pressure drop takes place so rapidly that solidification is not yet close, the pressure forces can outweigh the forces of cohesion of the molten mass, mainly viscosity forces, and bursting into a plurality of filament pieces (ligaments) occurs. The crucial factor here is that the thread must remain liquid at least in the interior so that this mechanism can set in. It has therefore also been proposed to further heat the monofilament after its emergence from the spinning nozzle.

Automatic bursting of a molten metal thread is also named the "NANOVAL effect" after the firm which uses it.

Defibration by bursting has become known in the manufacture of mineral fibres, thus in DE-A-33 05 810. By interfering with the gas flow in a rectangular channel arranged below the spinning nozzle by means of fittings which generate cross flows, as stated there the result is defibration of the single melt monofilament. In a not quite clear account there is mention of defibration by static pressure gradient in the air flow, and in fact in EP 0 038 989 drawing from a 'loop or zigzag movement ... after the fashion of a multiple whiplash effect'. The fact that the actual

'defibration' is caused by an increase in pressure in the interior of the thread and decrease in the surrounding gas flow was not recognised, nor any control mechanisms in this direction.

For polymers, this finding from mineral fibre manufacture was obviously made use of by the same applicant firm. In DE-A-38 10 596 in an apparatus according to Fig. 3 and description in example 4 the melt stream of polyphenylene sulphide (PPS) is 'defibrated by a high static pressure gradient'. The gas streams are hot, even heated beyond the melting point of the PPS. A static pressure gradient in the gas flow, decreasing in the direction of thread travel, cannot on its own defibrate the thread. It was not recognised that, for this, the melt stream must remain liquid in its interior, at least in an adequate portion. But by using hot air in the region of the polymer melt temperature, this happens by itself. It is not a 'pressure gradient occurring after the outlet holes', column 1, lines 54-55 that draws the melt streams into fine fibres, but a static pressure gradient between melt stream and surrounding gas flow that causes it to split or defibrate. The threads produced are of finite length and amorphous.

The threads of the method according to the invention on the other hand are endless or essentially endless. They are produced by selectively controlled bursting of a still molten monofilament in a laminar gas flow surrounding them, that is, without turbulence-generating cross flows. Basically all thread-forming polymers are considered, such as polyolefins PP, PE, polyester PET, PBT, polyamides PA 6 and PA 66 and others such as polystyrene. Here, those such as polypropylene (PP) and polyethylene (PE) are to be regarded as favourable because surface tension and viscosity are in a ratio which readily allows the build-up of an internal thread pressure against the surface tension force of the thread skin, while the viscosity is not so high that bursting is prevented. The ratio of surface tension to viscosity can be increased by increasing the melt temperature in most polymers. This takes place in a simple manner in melt manufacture and can be reinforced by heating the spinning nozzles shortly before emergence of the threads. Heating the threads afterwards by hot gas streams does not however take place according to the present invention.

It can be established that the subject of the invention, controlled splitting of a polymer thread drawn with cold air into a plurality of finer single threads of endless or essentially endless single threads, has not yet been found. This takes place by the automatic effect of bursting of the melt

thread due to a positive pressure difference between the hydraulic pressure in the thread, arising from the surface tension of the thread envelope, and the gas flow surrounding it. If the pressure difference is so great that the strength of the thread envelope is no longer sufficient to hold together the interior, then the thread bursts. Splitting into a plurality of finer threads occurs. The gas, usually air, can be cold, i.e. does not have to be heated, only the process conditions and the apparatus must be such that the melt monofilament in its critical diameter which depends on the melt viscosity and the surface tension of the polymer concerned is not cooled to such an extent that it can no longer burst due to the internal liquid pressure building up. Also the melt holes must not be cooled by the gas so greatly that the melt cools down too greatly, let alone already solidifies there. The process and geometrical conditions for producing this splitting effect are relatively easy to find.

The advantage of the present invention lies in that, in a simple and economical manner, very fine threads within a range of well below 10 μm , mainly between 2 and 5 μm , can be produced, which in the case of pure drawing for example by the melt-blow method can be accomplished only with hot gas (air) jets heated above melting point, and so requires considerably more energy. Moreover, the threads are not damaged in their molecular structure by excessive temperatures, which would lead to reduced strength, with the result that they can then often be rubbed out of a textile structure. Another advantage lies in that the threads are endless or quasi-endless and cannot protrude from a textile structure such as a non-woven fabric and come away as fuzz. The apparatus for carrying out the method according to the invention is simple. The spin holes of the spinning nozzle can be larger and so less susceptible to breakdowns, and the Laval nozzle cross-section in its precision does not need the narrow tolerances of the lateral air slots of the melt-blown method. For a given polymer one need only coordinate the melt temperature and the pressure in the chamber with each other, and with a given throughput per spin hole and the geometrical position of the spin holes relative to the Laval nozzle splitting occurs.

Practical examples of the invention are shown in the drawings and described in more detail in the description below. They show:

Fig. 1 a schematic sectional view of an apparatus for the manufacture of microthreads by means of cold gas jets by bursting of a melt stream into a plurality of single threads according to a first embodiment of the invention,

Fig. 2 a perspective partial view of the apparatus according to the invention in an embodiment with row nozzle and spin holes in nipple form for the manufacture of non-woven fabrics from microthreads, and

Fig. 3 a partial view in section of the spinning nozzle and Laval nozzle according to a third embodiment of the invention.

In Fig. 1 is shown an apparatus for the manufacture of essentially endless fine threads from melt-spinnable polymers, which comprises a spinning head or spinning beam 11, not described in more detail, in which is held a spinning nozzle 1. The spinning head 11 and the spinning nozzle are in a generally known manner composed of different parts, so that a description of them is omitted. The spinning head or spinning beam 11 is surrounded by a heating system 12 which is designed as a system for liquid or steam heating via chambers or as an electric band heating system. The spinning head or spinning beam is connected to melt-proportioning devices, not shown, such as spinning pumps and extruders, which are the usual devices for the manufacture of synthetic fibres, so that these are not described further either.

The spinning nozzle comprises a nozzle orifice 3 which comprises one, or usually several spin holes arranged in a row. Several parallel rows are possible too. Below the spinning head 11 is located a plate 6' with a gap 6 which is of convergent-divergent construction and widens greatly due to a space 7 located below it and forms a Laval nozzle. Depending on the shape of the spinning nozzle 1, the Laval nozzle 6 is constructed rotationally symmetrically similarly to a stop in the case of a single nozzle or as a longitudinal gap in the case of a row nozzle. The spinning nozzle or the spin holes of the spinning nozzle end just above the Laval nozzle 6 or in the plane of the plate 6', but the spinning nozzle 1 can also extend slightly into the Laval nozzle 6.

Between spinning head and plate 6' is located a closed chamber 8, to which gas is supplied in the direction of the arrows 5 for example by a compressor. The gas is usually at ambient

temperature, but can be at a slightly higher temperature, for example 70 to 80°, on account of the heat of compression from the compressor.

The nozzle orifice 3 is surrounded by an insulating assembly 9 which protects the nozzle orifice 3 against excessive heat losses due to the gas flow 5. In addition an electric band heating system 10 can be arranged between insulating assembly 9 and orifice 3.

The space 7 is usually at ambient pressure, while the gas in the chamber 8 is at an elevated pressure compared with the space 7. In the case of directly following further processing into a non-woven fabric or other thread structures, the space 7 can be at a slightly elevated pressure compared with ambient pressure, i.e. atmospheric pressure, for example a few mbar higher, which is needed for the further processing, such as non-woven fabric laying or other thread collecting devices.

The polymer melt is pressed in the direction of the arrow 2 out of the nozzle orifice 3 out of the spin hole or opening 4 as a melt monofilament, and is picked up by the gas jets 5 and tapered to smaller diameters by shear stresses at its circumference. As the basically cold gas streams, which can be air streams, cool it down, after a few millimetres it must pass into the narrowest region of the Laval nozzle and so into an area of lower pressure. As soon as the taper has progressed so far and due to the effect of the surface tension of the melt at the thread envelope the pressure in the interior has increased so far that it is above that of the gas flow, bursting of the monofilament occurs, namely when the thread envelope can no longer hold the melt thread together against the internal pressure which has increased with thread constriction. The melt monofilament is divided into single threads which, on account of the temperature difference between melt and cold gas or air and the suddenly greatly increased surface area of the single threads referred to the thread mass, cool down rapidly. Hence a given number of very fine essentially endless single threads is produced.

It follows from the nature of such bursting processes similar to explosions that the number of threads produced after the splitting point, which can be for example 5 to 25 mm below Laval nozzle 6, cannot be constant. Because of the short distance which thread and gas together cover up to the splitting point, the flow interface around the thread is laminar. Preferably also the air

from the supply pipes is conducted in laminar fashion as far as possible to the region of splitting. This has the advantage of the lower flow losses and hence the lower energy requirements which distinguish laminar flows compared with turbulent ones, but also a more uniform time curve of splitting, because disturbances due to turbulent changes are absent. The accelerated flow such as is present in the cross-section of the Laval nozzle 6 remains laminar and can even be laminarised if a certain turbulence prevailed before.

The added advantage of laminar drawing of the melt monofilament up to the splitting point and also beyond it leads to splitting into more uniform single threads, because there are not greater differences in the flow rate and hence in the sheer stress acting on the melt monofilament and resulting single threads and in the pressure of gas flow. The distribution of the thread diameters is, as it turned out surprisingly, very narrow, e.g. propylene threads whose diameters are all between 2 and 4 μm can be produced.

As already stated above, the speed of gas flow in the direction of the arrows 5 increases constantly towards the spin hole 4 and then in the Laval nozzle 6. In the narrowest cross-section of the Laval nozzle it can increase up to the speed of sound if the critical pressure ratio, depending on the gas, is reached, and in the case of air the ratio between the pressure in the chamber 8 and the space 7 is around 1.9.

The threads move downwards in the direction of the arrows 21 and for example can be deposited on a belt, not shown, to form a non-woven fabric, or otherwise further treated.

In Fig. 2 is shown a further example of the present invention, in which the spinning nozzle 1 is constructed as a row nozzle. Here are shown in particular the outlet points of the spinning nozzle 1 with orifice 3 which comprises nipples 25. This form allows concentric access of the gas to the melt monofilament, which proved to be advantageous for splitting, both with respect to the obtainable fineness of the threads and with respect to the width of fluctuation of their diameters.

By contrast with the band heating system 10 according to Fig. 1, here round heating elements 26 are shown for the supply of heat to the nozzle orifice 3 which is shielded by insulators 27 from the gas flow 5. The threads leave the Laval nozzle in a wide curtain together with the gas, and

move in the direction of the arrows 21 towards a collecting belt 20 and are deposited in the region 22 to form a non-woven fabric 23. The non-woven fabric 23 leaves the area of its manufacture in the direction of arrow 24.

A further embodiment of the spinning and splitting apparatus according to the invention is shown in Fig. 3. Here again the melt monofilament is expelled from an insulated nozzle orifice 3 with one or more melt holes 4 and picked up by the laterally applied gas stream 5 and drawn in length into thinner diameters by shear stress forces. In the plate 6' in the region of the Laval nozzle 6 a heating device 30 is incorporated. On the way to the narrowest cross-section of the Laval nozzle 6, therefore, the melt monofilament has heat supplied to it by radiation. As a result, cooling by the basically cold air/gas streams is delayed. The melt monofilament passes, drawn to a smaller diameter, into the partial-pressure area of the Laval nozzle 6 and can split into even finer single threads.

The following examples describe methods and apparatuses with the essential process data used with different raw materials and the thread results.

Example 1

By means of a laboratory extruder (screw with a diameter of 19 mm and $L/D = 25$) for the processing of polymers, polypropylene (PP) with a MFI (melt flow index) of 25 (230°C , 2.16 kg) was melted and supplied via a gear spinning pump to a spinning head with a nozzle orifice 3 comprising seven holes 4 arranged in a row at equal intervals of 4.5 mm each, with a diameter of the holes 4 of 1 mm. The melt-conducting pipes were heated from the outside by electric band heating systems. The nozzle orifice 3 was insulated according to Fig. 1 at its flanks by a ceramic insulator 9 (calcium silicate) against the gas flow below it and heated with electric heating systems. Below the spinning nozzle 1 was located the chamber 8 for gas supply. Air which was taken from a compressed air network and fed into the latter by a compressor was taken as the gas in this and the other examples. The chamber 8 was defined at the bottom by a plate which had a slot forming the Laval nozzle 6 with a width of 4 mm at its narrowest cross-section. The lateral supply cross-sections for the air in the chamber had a height of 32 mm, measured from the upper edge of the Laval nozzle plate 6'. The outlet openings of the holes 4 were arranged exactly at the

level of the upper edge of the Laval nozzle plate 6' and had a distance of 10 mm from the narrowest cross-section of the Laval nozzle 6.

Melt pressure and temperature between spinning pump and connecting piece to the spinning nozzle 1 were measured with a strain-gauge pressure measuring device (Dynisco, model MDA 460) or a thermoelement.

Characterisation of the threads obtained is by the thread diameter d_{50} averaged over 20 single measurements, and if required also by the standard deviation s .

Splitting is characterised by the theoretical thread count N . This indicates how many single filaments of the measured average thread diameter d_{50} must move at the maximum possible speed through the narrowest cross-section of the Laval nozzle 6 in order to convert the measured melt mass to single filaments. The maximum possible speed is the gas speed in the narrowest cross-section of the Laval nozzle 6, which is either the speed of sound which can be calculated from the conditions in the chamber 8 or, in the event that the critical pressure ratio which is needed to attain the speed of sound is not attained, can be calculated from these conditions with Saint-Venant and Wantzell's formula. If the theoretical thread count N is more than 1, the thread diameter observed cannot have been produced simply by drawing, this would be contrary to the law of preservation of mass. For the observed theoretical thread counts N well over 1, only splitting is possible as an explanation. A multiple whiplash effect can perhaps explain values just over 1 to 10, but not the observed values of up to 627. As the actual thread speed must be below the maximum, the single filament number actually obtained will be above the theoretical number.

At a melt temperature of 340°C and a melt pressure between spinning pump and connecting piece to the spinning nozzle 1 of approximately 1 bar above the pressure in the pressure 8, which was approximately also the pressure in front of the spinning capillaries, and with a quantity proportioned via the spinning pump of 43.1 g/min, that is, 6.2 g/min per hole, the following thread values resulted at the different pressures in the chamber 8 above the atmospheric pressure in space 7:

0.25 bar	$d_{50} = 7.6 \mu\text{m}$, $N = 123$
0.5 bar	$d_{50} = 4.4 \mu\text{m}$, $N = 276$
1.0 bar	$d_{50} = 3.9 \mu\text{m}$, $N = 283$

If only 4.6 g/min are passed through instead of 6.2 g/min per hole, at a pressure in the chamber 8 of 0.5 bar a d_{50} of 3.0 μm instead of 4.4 μm is obtained.

How important exact coordination of melt temperature, melt quantity and gas flow is, is shown by the following example of a distance between the holes 4 of 15 mm, a throughput per hole 4 of 4.6 g/min and a pressure in the chamber 8 of 0.5 bar:

melt temperature 340°C	$d_{50} = 3.0 \mu\text{m}$, $s = 0.8 \mu\text{m}$, $N = 187$
melt temperature 305°C	$d_{50} = 8.2 \mu\text{m}$, $s = 4.7 \mu\text{m}$, $N = 25$.

Clearly conditions are such that around the monofilaments there has already formed a cold envelope which greatly hinders splitting. Not the whole monofilament is split open, but only a portion, which can be seen by the fact that, although the minimum observed thread diameter has not changed (some therefore split open), some single filaments with a diameter of more than 10 μm occur. Thus no splitting has occurred there. At the higher temperature, on the other hand, all single filaments are between 1.6 μm and 4.8 μm . The greater variance of thread diameters is reflected in the much greater standard deviation.

A design of the orifice 3 with nipples 25 according to Fig. 2 allows the manufacture of much finer threads with a smaller width of fluctuation and/or a distinct increase in throughput. Thus, for a temperature of 370°C, a distance between holes 4 of 15 mm, a distance from outlet openings of the holes 4 to the narrowest cross-section of the Laval nozzle of 8.5 mm (the outlet openings are submerged 1.5 mm in the imaginary plane of the Laval nozzle plate) and a pressure in the chamber 8 of 0.75 bar, the following thread values are obtained:

6.2 g/min per hole	$d_{50} = 2.1 \mu\text{m}$, $s = 0.30 \mu\text{m}$, $N = 445$
12.3 g/min per hole	$d_{50} = 2.5 \mu\text{m}$, $s = 0.60 \mu\text{m}$, $N = 627$

Example 2

With the apparatus from example 1, polyamide 6 (PA6) with a relative viscosity $\eta_{rel} = 2.4$ was fed to a nozzle orifice 3 with 58 holes 4 at intervals of 1.5 mm and with a diameter of 0.4 mm. The distance from the outlet openings of the holes 4 to the narrowest cross-section of the Laval nozzle was 12.0 mm (the outlet openings ended 2.0 mm above the imaginary plane of the Laval nozzle plate). With a throughput per hole 4 of 0.25 g/min and a pressure in the chamber 8 of 0.02 bar above the environment, filaments with a mean diameter d_{50} of 4.1 μm were produced.

Example 3

With the apparatus from example 1, polypropylene (PP) with a MFI of 25 (230°C, 2.16 kg) was fed to a nozzle orifice 3 with three holes 4 at intervals of 15 mm and with a diameter of 1.0 mm. Individual rotationally symmetrical Laval nozzles 6 were arranged in the Laval nozzle plate 3 coaxially with the three holes 4. The outlet openings of the holes 4 were arranged exactly at the level of the upper edge of the Laval nozzle plate and had a distance of 4.5 mm from the narrowest cross-section of the Laval nozzles 6. At a pressure in the chamber 8 of 0.75 bar above the environment 7 and with a throughput per hole 4 of 9.3 g/min, single filaments with a mean diameter d_{50} of 4.9 μm were produced. In this case a theoretical thread count of 123 results.

Of interest in this manner of operation is the observation that the bursting point compared with example 1 has clearly shifted in the direction of the narrowest cross-section of the Laval nozzles 6. Whereas in the case of the slot-like Laval nozzle 6 this point is about 25 mm below the narrowest cross-section, the distance in the case of the rotationally symmetrical Laval nozzle 6 is only about 5 mm. The observation is explained by the fact that, due to the rotationally symmetrical enclosure of the melt thread, higher shear stresses were transmitted to it, and therefore it is drawn more rapidly to the smaller diameter yielding the bursting point. Moreover, the pressure in the free jet after leaving the Laval nozzle 6 does not drop suddenly to the ambient pressure, but only after a certain running length. The free jet characteristics are however in the planar case different to those in the rotationally symmetrical case.

Patent claims

1. Method for the manufacture of essentially endless fine threads from meltable polymers, in which polymer melt is spun from at least one spin hole and passed through a Laval nozzle, wherein the spun thread is drawn by gas streams accelerated to high speed by means of the Laval nozzle, and wherein with a given geometry of the melt hole and its position relative to the Laval nozzle the temperature of the polymer melt, its throughput per spin hole and the pressures in front of and behind the Laval nozzle which define the speed of the gas streams are controlled in such a way that the thread before solidification thereof attains a hydrostatic pressure in its interior which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.
2. Method according to claim 1, characterised in that the gas flow around the at least one thread is laminar.
3. Method according to claim 1 or claim 2, characterised in that the space behind the Laval nozzle is at ambient pressure or, in case of further processing of the threads, is at a pressure slightly above ambient pressure, which is necessary for further processing.
4. Method according to any of claims 1 to 3, characterised in that the gas streams which draw the thread are at ambient temperature or a temperature caused by their supply.
5. Method according to any of claims 1 to 4, characterised in that the ratio of the pressures in the space above and below the Laval nozzle when using air is selected between 1.02 and 2.5, depending on the polymer, its throughput and melting temperature.
6. Method according to any of claims 1 to 5, characterised in that the thread emerging from the spin hole is heated by radiation in the region of the Laval nozzle.
7. Method according to any of claims 1 to 6, characterised in that a plurality of threads are spun and split, which are deposited to form a non-woven fabric of further processed into yarns.

8. Apparatus for carrying out the method according to any of claims 1 to 7 with a spinning head connected to a feeder for the melt, a spinning nozzle assembly which is held in the spinning head and comprises at least one spin hole and which spins a melt monofilament, a plate (6') which is located below the spinning head (11) and which comprises a Laval nozzle (6) arranged in a fixed geometrical relationship to the spin hole (4), wherein between plate (6') and spinning head (11) is formed a closed first space (8) provided with a supply of gas (5) and below the plate (6') is provided a second space (7), and wherein the throughput of the melt per spin hole (4), the temperature of the melt and the pressure in the first and second spaces are adjusted in such a way that the spun melt monofilament carried by the flow of gas after leaving the Laval nozzle (6) before solidification thereof attains a hydrostatic pressure which is greater than the gas pressure surrounding it, such that the thread bursts and splits into a plurality of fine threads.
9. Apparatus according to claim 8, characterised in that the spinning assembly (3) is insulated from the first space (8) in the region of the at least one spin hole (4) by an insulating assembly (9) and/or is heated in the region of the at least one spin hole (4).
10. Apparatus according to claim 8 or 9, characterised in that the pressure ratios in the first and second spaces (8, 7) are adjusted in such a way that the gas flow in the Laval nozzle (6) attains speeds up to the speed of sound and over.
11. Apparatus according to any of claims 8 to 10, characterised in that the second space (7) is at ambient pressure or a few mbar over.
12. Apparatus according to any of claims 8 to 11, characterised in that the supplied gas is at ambient temperature or the temperature of its feeder.
13. Apparatus according to any of claims 8 to 12, characterised in that the outlet opening of the at least one spin hole (4) in the region of the Laval nozzle (6) is located at the level of the upper edge of the plate (6'), a few mm above the upper edge of the plate, or extends a few mm into the Laval nozzle (6).

14. Apparatus according to any of claims 8 to 13, characterised in that the spinning nozzle assembly comprises a plurality of spin holes (4) which are if occasion arises provided with nipples and which form a row or several parallel rows.
15. Apparatus according to any of claims 8 to 14, characterised in that the plate comprises at least one elongate Laval nozzle.
16. Apparatus according to any of claims 8 to 14, characterised in that the plate comprises a plurality of rotationally symmetrical Laval nozzles.
17. Apparatus according to any of claims 8 to 16, characterised in that a delivery belt is provided for deposition of the threads and formation of a non-woven fabric.
18. Apparatus according to any of claims 8 to 16, characterised in that a winding device is provided for winding the threads.
19. Non-woven fabric made from threads which have been produced by the method according to any of claims 1 to 7.
20. Yarns made from threads which have been produced by the method according to any of claims 1 to 7.




Fig. 1





Fig. 2

*Fig. 3*

**COMBINED DECLARATION
AND POWER OF ATTORNEY****(Original, Design, National Stage of PCT, Divisional, Continuation or C-I-P Application)**

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name; I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled:

"METHOD AND DEVICE FOR THE PRODUCTION OF AN ESSENTIALLY CONTINUOUS FINE THREAD"

This declaration is of the following type:

- ☐ original
- ☐ design
- ☒ national stage of PCT.
- ☐ divisional
- ☐ continuation
- ☐ continuation-in-part (C-I-P)

the specification of which: *(complete (a), (b), or (c))*

- (a) ☐ is attached hereto.
- (b) ☒ was filed on June 21, 2000 as Application Serial No. PCT/EP00/05703.
- (c) ☐ was described and claimed in PCT International Application No. filed on and was amended on *(if applicable)*.

Acknowledgement of Review of Papers and Duty of Candor

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose information which is material to the patentability of the subject matter claimed in this application in accordance with Title 37, Code of Federal Regulations § 1.56.

☐ In compliance with this duty there is attached an information disclosure statement. 37 CFR 1.98.

Priority Claim

I hereby claim foreign priority benefits under Title 35, United States Code, § 119(a)-(d) of any foreign application(s) for patent or inventor's certificate or of any PCT International Application(s) designating at least one country other than the United States of America listed below and have also identified below any foreign application(s) for patent or inventor's certificate or any PCT International Application(s) designating at least one country other than the United States of America filed by me on the same subject matter having a filing date before that of the application on which priority is claimed

Attorney Docket No. 073306.0101

(complete (d) or (e))

- (d) ☐ no such applications have been filed.
(e) ☒ such applications have been filed as follows:

PRIOR FOREIGN PCT APPLICATION(S) FILED WITHIN 12 MONTHS (6 MONTHS FOR DESIGN) PRIOR TO SAID APPLICATION			
COUNTRY	APPLICATION NO.	DATE OF FILING (day, month, year)	DATE OF ISSUE (day, month, year)
PCT/EP00/04838		June 21, 2000	
ALL FOREIGN APPLICATION(S), IF ANY, FILED MORE THAN 12 MONTHS (6 MONTHS FOR DESIGN) PRIOR TO SAID APPLICATION			
GERMANY	199 29 709.6	June 24, 1999	

Claim for Benefit of Prior U.S. Provisional Application(s)

I hereby claim the benefit under Title 35, United States Code, § 119(e) of any United States provisional application(s) listed below:

Provisional Application Number	Filing Date

Claim for Benefit of Earlier U.S./PCT Application(s) under 35 U.S.C. 120

(complete this part only if this is a divisional, continuation or C-I-P application)

I hereby claim the benefit under Title 35, United States Code, § 120 of any United States application(s) or PCT international application(s) designating the United States of America that is/are listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior application(s) in the manner provided by the first paragraph of Title 35, United States Code § 112, I acknowledge the duty to disclose information as defined in Title 37, Code of Federal Regulations, § 1.56 which occurred between the filing date of the prior application(s) and the national or PCT international filing date of this application:

PCT/EP00/05703	June 21, 2000	Pending
(Application Serial No.)	(Filing Date)	(Status) (patented, pending, abandoned)

(Application Serial No.)

(Filing Date)

(Status) (patented, pending, abandoned)

Power of Attorney

As a named inventor, I hereby appoint

R. William Beard, Jr.: 39,903	Ronald L. Chichester: 36,765	Claude E. Cooke, Jr.: 34,142	Roger J. Fulghum: 39,678
Michael A. Hawes: 38,487	Carrey J. Hetherington: 47,646	Paul N. Katz: 35,917	Michael G. Lockler: 44,878
Mitchell D. Lukin: 30,772	Jerry W. Miller: 23,008	Paul R. Morico: 35,960	Paul Asketman: 39,891
Scott F. Penridge: 28,142	Bruce W. Slayden, II: 33,790	Howard L. Speight: 37,733	Lori D. Stiffler: 36,939
Khanan Sentharam: 45,144	Melissa J. Szanto: 40,834	G. Alan Witz: 36,061	

HOU03;#2048E.1

Attorney Docket No. 073306.0101

Please direct all communications to: Baker Botts L.L.P., One Shell Plaza, 910 Louisiana Street, Houston, Texas 77002-4995, 713.229.1786, Fax: 713.229.7886, attention of: Bruce W. Slayden, II, as attorneys to prosecute this application and to transact all business in the Patent and Trademark Office connected therewith.

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

FULL NAME OF SOLE OR FIRST INVENTOR	LAST NAME Gerking	FIRST NAME Lüder	MIDDLE NAME
RESIDENCE & CITIZENSHIP	CITY Berlin <i>DEX</i>	STATE or FOREIGN COUNTRY Germany	COUNTRY OF CITIZENSHIP German
POST OFFICE ADDRESS	POST OFFICE ADDRESS Hohe Ahren 1	CITY Berlin	STATE or COUNTRY Germany
DATE ✓ Dec. 20, 2001	SIGNATURE OF INVENTOR <i>[Signature]</i>		
ZIP CODE 14195			

Check proper box(es) for any added page(s) forming a part of this declaration

- ☐ Signature for ninth and subsequent joint inventors. Number of pages added _____
- ☐ Signature by administrator(trix), executor(trix) or legal representative for deceased or incapacitated inventor. Number of pages added _____
- ☐ Signature for inventor who refuses to sign, or cannot be reached, by person authorized under 37 CFR 1.47. Number of pages added _____